CONTACT

RICHARD LAING

richard@gmscn.com

+447503868856

SERVICE PROFILE INCINERATOR OVERHAUL





PREPARATION

Discuss safety protocols with Chief Engineer.

Inspect chamber, door and mechanical fixtures.





PROCESS

Remove refractory bricks, insulation and any remaining refuse. Replace bricks, reline with insulation provided by original equipment manufacturer.





COMPLETION

Rebuild furnace door.

Restart and test function.

Service report complete with pictures of each stage provided

Approved by Chief Engineer.